

Target Group Procedure

Procedure Number	TGT-PROC-17-004
Revision	0
Active Date	7/27/2017
Expiration Date	7/27/2017
Author	David Meekins
Checked	Jenord Alston
Approved	David Meekins
Tittle	HATT Tritium Cell Examination, Assembly, and Testing Procedure
Description:	

Procedure for examination, assembly, and testing the tritium cell(s) for PS-TGT-12-001. Results shall be marked on the procedure and filed for each cell assembly. Activities are:

- Receipt Inspection of parts
 - Dimensional inspection
 - Visual surface inspection
- Thickness measurements
- Torque record
- Leak/pressure testing



1. Revision History

Revision	Date	Description
Revision: 0	7/26/2017	Original

2. Definitions

• HATT: Hall A Tritium Target

3. Purpose and Scope

The purpose of this procedure is to ensure proper cleaning, assembly, testing, and documentation of the HATT cell. The report generated as part of the process steps for this procedure shall serve as the final mechanical examination for the cell. Reference the JLAB drawing TGT-103-1000-0013 and other drawings referenced therein.

4. Facility

This procedure shall be performed in the JLAB Target Group Shop area.

5. Authority

The following JLAB Target Group members shall have authority to implement this procedure.:

- Chris Keith Target Group Lead
- David Meekins Target Group Staff Scientist
- Jenord Alston JLAB Examiner

Alterations to this procedure shall be approved by David Meekins or Chris Keith.

6. Process Steps

The following process steps shall be completed as part of this procedure:

- 1. All components shall be cleaned using procedure TGT-PROC-17-003 Rev 0.
- 2. Swagelok MS-TL-SGT anti-seize shall be applied to all fastener threads.
- 3. Calibrate the MagnaMike to be used in the next step.
- 4. Use MagnaMike to perform dimensional checks and thicknesses of thin sections and record results on report form.
 - a. Measure main body beam left side wall thickness at using 10 measurements at each location: upstream, mid and downstream as shown in the figure below. Record the average and standard deviation on the report form below.
 - b. Measure main body beam right side wall thickness at using 10 measurements at each location: upstream, mid and downstream as shown in the Figure 1 below. Record the average and standard deviation on the report form below.
 - c. Measure beam exit of main body. Record the average and standard deviation on the report form below.



- d. Measure entrance window thickness (see Figure 2). Record the average and standard deviation on the report form below.
- 5. Check calibration of the torque wrenches to be used in the assembly of the HATT cell.
- 6. Check and record assembly torque data and record on report form.
- 7. Perform reverse He leak tests of cell assembly with 400 psia in cell. Record data on report form.
- 8. Perform valve leak through test will cell filled at 200 psia helium. Record data on report form.
- 9. Perform cold leak test using PS-TGT-16-002 Target Group Cryo Test Stand with cell filled to 200 psia helium. Record data on report form.
- 10. Remove helium pressure on cell. Maintain slight positive pressure ~ 1 psig in cell for shipping to SRS.
- 11. Procedure complete




Figure 1: Main body measurement locations




Figure 2: Entrance window measurement location



HATT Assembly, Testing, and Examination Report

General							
Examiner							
Date							
Cell assembly number							
Assembly Tech							
Entrance window number							
Main body number							
Surface finish							
Parameter	Data						
General condition free of nicks	☐ Yes	□ No					
scratches dents etc.							
Components cleaned per procedure	☐ Yes	□ No					
TGT-PROC-0017-003							
Are external dimensions within	☐ Yes	□ No					
tolerance							
Tapped holes run free	☐ Yes	□ No					
MagnaMike Calibrated Prior to start	☐ Yes	□ No					
Beam left upstream thickness (mm)							
Beam left upstream thickness (mm)							
Beam left upstream thickness (mm)							
Beam right upstream thickness (mm)							
Beam right upstream thickness (mm)							
Beam right upstream thickness (mm)							
Beam exit thickness (mm)							
Entrance window thickness (mm)							
Heat/lot cell main body							
Heat/lot cell entrance window							
Heat/lot ¼-28 hardware							
Heat/lot 8-32 screws							
Heat/lot 4-40 screws							
Weld exam performed	□ VT	\square RT					
Continue to leak testing section							



Pressure and Leak Testing									
Leak Test (ASME B31.3 (2014) 345.5)									
Test date: St		Start time:	Start time:		Actual gauge pressure:				
Required Duration: Fin		Finnish time:	nnish time:						
15 min									
TEST EQUIPMENT									
Gauge Type/Number:	Rang	e:	Cal date: C		al due date (attach cert if needed)				
Helium Leak Testing	ı:								
Note maximum leak	rate	warm is 10	⁹ mbar l/s. Req	uir	ed leak rate col	d is 10 ⁻⁷			
mbar I/s.									
Helium leak detector calibrated					□ No				
Valve assembly capped or		or Cell press	Cell pressure:		Leak Rate				
connected to hose									
Valve closed with VCR cap		p Cell press	Cell pressure:		Leak Rate				
removed									
Cold leak test with VCR		Cell pressure warm:		Leak Rate					
cap installed									
Signature Block									
Examiner:									
Design Authority:									
Pressure Test Technician									
Examination Result									
(pass/fail)									